

Panel height 9'

For panel height 9':

7 cross stiffeners, of which 7 are multi-function profiles with welded DW-threaded nuts. 3 symmetrically arranged tie holes per panel height.

Attention

Unused tie holes need to be closed with plugs D 27/30.

